

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer

SCHEDULE-B

NAME OF WORK:Filling Potholes in asphalt roads in ward no 70

Sl.No	Description of work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Words (Rs.)
1	Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications and as per the direction of Engineer-in-charge of the work..	Cum	221.2	2241.43 2251.44	
2	Filling Pot-holes and patch repairs with bituminous concrete, 40 mm, KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 back filling the pot hole with bituminous material as per clause 500.4 compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications and as per the direction of Engineer-in-charge of the work.	Sqm	1106	409.58 411.41	

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,